

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR CONSTRUCTION OF BOUNDRY WALL FOR
PROTECTION AND SAFTY OF INSPECTION HOUSE CAMPUS & LAND
AT NEHTAUR BARRAGE IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : INSPECTION HOUSE AT NEHTAUR BARRAGE IN DISTT. BIJNOR.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in excavation in foundation in dry soil i/c lift 1.50M and lead upto 30M i/c all cost of material, labour T&P etc. complete.	400.00	M ³		
2.	S/Laying P.C.C. 1:4:8 in foundation for making base i/c all cost of material, labour T&P etc. complete.	60.00	M ³		
3.	P/Laying D.P.C. 20mm thick 1:2 course sand.	110.00	M ²		
4.	I st class Brick work in 1:4 C.M. of Boundry wall i/c all cost of material, labour T&P etc. complete.	450.00	M ³		
5.	12 mm Thick Cement Plaster in 1:4 Cement mortar on brick work i/c all cost of material, labour T&P etc. complete.	2000.00	M ²		
6.	S/Fixing of Iron Gate	1	No.		

Sign of Contractor

Address

.....
.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Work : RENOVATION OF INSPECTION HOUSE AT NEHTAUR BARRAGE IN
DISTT. BIJNOR FOR THE YEAR 2016-17

Site of Work : INSPECTION HOUSE AT NEHTAUR BARRAGE

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1	Dismantling old Plaster i/c raking out joints and disposal of debris within 60 meters distance.	1300.00	M ²		
2	Dismantling Door or window i/c chaukhats with hold fast and i/c stacking of materials with in a distance of 60M.	25.00	M ²		
3	Dismantling Door or window leaves i/c stacking of materials with in a distance of 60M.	25.00	M ²		
4	12 mm Thick Cement Plaster in 1:4 Cement mortar on brick work i/c all cost of material, labour T&P etc. complete.	3300.00	M ²		
5	Providing & Laying wall putty on wall 2 coat	800.00	M ²		
6	Providing and laying Cement Primer in two coats new/old surface i/c all cost of material, labour T & P etc. complete.	3300.00	M ²		
7	Painting with plastic emulsion paints in two coat cost of all material, labour T&P etc. complete.	800.00	M ²		
8	Painting 2 coates Apax ultimate exterior paint(Tera cota) i/c all cost of material, labour T & P etc. complete.	2500.00	M ²		
9	Supplying & Fixing flush door of 32mm thick with chaukhat i/c all cost of material, labour T&P etc. complete.	25.00	M ²		
10	Supplying & Fixing Jali door/window with shisham wood fram i/c all cost of material, labour T&P etc. complete.	25.00	M ²		
11	Painting 2 coates enamel paint on door & window i/c all cost of material, labour T&P etc. complete.	110.00	M ²		
12	Painting 2 coates Apcolite steel paint (Apax) i/c all cost of material, labour T & P etc. complete.	20.00	M ²		

Sign of Contractor

Address
.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR LAYING INTER LOCKING TILES ON TOP OF PILI BUNDH FROM KM. 1.100 TO KM. 8.000 IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : K.M 1.100 to 1.50 of PILI BUNDH.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in filling for Top and D/s Slope of Pili Bundh i/c all lift and lead beyond 1.00 km with ramming and dressing etc. complete.	2050.00	M ³		
2.	Laying Cement Concrete in 1 : 3 : 6 i/c all cost of material, Labour, T & P etc. complete.	90.00	M ³		
3.	Laying Cement Concrete in 1 : 2 : 4 i/c all cost of material, Labour, T & P etc. complete.	45.00	M ³		
4.	First Class (M-100) Brick work in 1 : 4 Cement mortar i/c all cost of material, Labour, T & P etc. complete	90.00	M ³		
5.	Supplying and Laying Shingle 10-20 mm Size on top of pili bundh i/c all cost of material, Labour, T & P etc. complete.	150.00	M ³		
6.	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	1500.00	M ²		
7.	12 mm thick Cement Plaster in 1 : 4 on brick work i/c all cost of material, Labour, T & P etc. complete	625.00	M ²		

Sign of Contractor
Address

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR LAYING INTER LOCKING TILES ON TOP OF PILI BUNDH FROM KM. 1.100 TO KM. 8.000 IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : K.M 1.50 to 2.00 of PILI BUNDH.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in filling for Top and D/s Slope of Pili Bundh i/c all lift and lead beyond 1.00 km with ramming and dressing etc. complete.	2050.00	M ³		
2.	Laying Cement Concrete in 1 : 3 : 6 i/c all cost of material, Labour, T & P etc. complete.	90.00	M ³		
3.	Laying Cement Concrete in 1 : 2 : 4 i/c all cost of material, Labour, T & P etc. complete.	45.00	M ³		
4.	First Class (M-100) Brick work in 1 : 4 Cement mortar i/c all cost of material, Labour, T & P etc. complete	90.00	M ³		
5.	Supplying and Laying Shingle 10-20 mm Size on top of pili bundh i/c all cost of material, Labour, T & P etc. complete.	150.00	M ³		
6.	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	1500.00	M ²		
7.	12 mm thick Cement Plaster in 1 : 4 on brick work i/c all cost of material, Labour, T & P etc. complete	625.00	M ²		

Sign of Contractor

Address

.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR LAYING INTER LOCKING TILES ON TOP OF PILI BUNDH FROM KM. 1.100 TO KM. 8.000 IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : K.M 2.00 to 2.50 of PILI BUNDH.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in filling for Top and D/s Slope of Pili Bundh i/c all lift and lead beyond 1.00 km with ramming and dressing etc. complete.	2050.00	M ³		
2.	Laying Cement Concrete in 1 : 3 : 6 i/c all cost of material, Labour, T & P etc. complete.	90.00	M ³		
3.	Laying Cement Concrete in 1 : 2 : 4 i/c all cost of material, Labour, T & P etc. complete.	45.00	M ³		
4.	First Class (M-100) Brick work in 1 : 4 Cement mortar i/c all cost of material, Labour, T & P etc. complete	90.00	M ³		
5.	Supplying and Laying Shingle 10-20 mm Size on top of pili bundh i/c all cost of material, Labour, T & P etc. complete.	150.00	M ³		
6.	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	1500.00	M ²		
7.	12 mm thick Cement Plaster in 1 : 4 on brick work i/c all cost of material, Labour, T & P etc. complete	625.00	M ²		

Sign of Contractor

Address

.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR LAYING INTER LOCKING TILES ON TOP OF PILI BUNDH FROM KM. 1.100 TO KM. 8.000 IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : K.M 2.50 to 3.00 of PILI BUNDH.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in filling for Top and D/s Slope of Pili Bundh i/c all lift and lead beyond 1.00 km with ramming and dressing etc. complete.	2050.00	M ³		
2.	Laying Cement Concrete in 1 : 3 : 6 i/c all cost of material, Labour, T & P etc. complete.	90.00	M ³		
3.	Laying Cement Concrete in 1 : 2 : 4 i/c all cost of material, Labour, T & P etc. complete.	45.00	M ³		
4.	First Class (M-100) Brick work in 1 : 4 Cement mortar i/c all cost of material, Labour, T & P etc. complete	90.00	M ³		
5.	Supplying and Laying Shingle 10-20 mm Size on top of pili bundh i/c all cost of material, Labour, T & P etc. complete.	150.00	M ³		
6.	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	1500.00	M ²		
7.	12 mm thick Cement Plaster in 1 : 4 on brick work i/c all cost of material, Labour, T & P etc. complete	625.00	M ²		

Sign of Contractor

Address

.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project : PROJECT FOR LAYING INTER LOCKING TILES ON TOP OF PILI BUNDH FROM KM. 1.100 TO KM. 8.000 IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : K.M 3.00 to 3.50 of PILI BUNDH.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in filling for Top and D/s Slope of Pili Bundh i/c all lift and lead beyond 1.00 km with ramming and dressing etc. complete.	2050.00	M ³		
2.	Laying Cement Concrete in 1 : 3 : 6 i/c all cost of material, Labour, T & P etc. complete.	90.00	M ³		
3.	Laying Cement Concrete in 1 : 2 : 4 i/c all cost of material, Labour, T & P etc. complete.	45.00	M ³		
4.	First Class (M-100) Brick work in 1 : 4 Cement mortar i/c all cost of material, Labour, T & P etc. complete	90.00	M ³		
5.	Supplying and Laying Shingle 10-20 mm Size on top of pili bundh i/c all cost of material, Labour, T & P etc. complete.	150.00	M ³		
6.	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	1500.00	M ²		
7.	12 mm thick Cement Plaster in 1 : 4 on brick work i/c all cost of material, Labour, T & P etc. complete	625.00	M ²		

Sign of Contractor

Address

.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

Name of Project :PROJECT FOR CONSTRUCTION OF BOUNDRY WALL FOR
PROTECTION AND SAFTY OF RAMGANGA CANAL COLONY
DHAMPUR IN DISTT. BIJNOR FOR THE YEAR 2016-17

Name of Site : DIVISION OFFICE, RESIDANCE NO E-1 & E-2 OF RAM GANGA CANAL
COLONY DHAMPUR IN DISTT. BIJNOR.

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in excavation in foundation in dry soil i/c lift 1.50M and lead upto 30M i/c all cost of material, labour T&P etc. complete.	440.00	M ³		
2.	Laying P.C.C. 1:4:8 in foundation for making base i/c all cost of material, labour T&P etc. complete.	85.00	M ³		
3.	Laying D.P.C. 20mm thick 1:2 course sand.	132.00	M ²		
4.	Painting on D.P.C. with two coat bitumen 80/50 or 85/25 about 1.7 kg/M ² i/c cost of fuel, labour T&P etc. complete	132.00	M ²		
5.	I st class Brick work in 1:4 C.M. of Boundry wall i/c all cost of material, labour T&P etc. complete.	810.00	M ³		
6.	12 mm Thick Cement Plaster in 1:4 Cement mortar on brick work i/c all cost of material, labour T&P etc. complete.	2500.00	M ²		
7.	Snowcem washing in two coats for New surface i/c all cost of material, labour, T & P etc. complete.	2175.00	M ²		
8.	Laying 40mm thick C.C. Flooring finished with a floating coat of neat cement i/c all cost of material, labour T&P etc. complete.	60.00	M ²		
9.	Laying R.C.C. 1 : 2 : 4 i/c all cost of material, labour T&P etc. complete. But excluding cost of steel and Centring and Shuttering	6.00	M ³		
10.	Fabrication of steel gates with fixing i/c all cost of material, cutting, welding, labour T & P etc. complete.	800.00	Kg.		
11.	Ordinary Centring and Shutrting for R.C.C. work i/c all cost of material, labour T&P etc. complete	3.80	M ²		
12.	Bending, Binding, Cutting, Placing of reinforcement i/c cost of labour T&P etc. complete.	975.00	Kg.		
13.	Applying Ready mix primer on steel gate i/c all cost of material, labour, T & P etc. complete.	4.00	M ²		
14.	Painting 2 coates enamel paint on Steel gate i/c all cost of material, labour T&P etc. complete.	4.00	M ²		

Sign of Contractor

Address

.....

AFZALGARH IRRIGATION DIVISION, DHAMPUR

NAME OF WORK:- COSTRUCTION OF C.C. ROAD AND DRAIN.

NAME OF ESTIMATE : PROJECT FOR CONSTRUCTION OF ROAD AND SIDE DRAINS AT RAMGANGA COLONY DHAMPUR IN DISTT. BIJNOR FOR THE YEAR 2016-17

REACH : FROM MAIN GATE OF COLONY TO H.NO. C-17 AND FROM H.NO. B-9 TO TEHSIL ROAD IN RAMGANGA COLONY DISTT. BIJNOR

SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1	Earth work in excavation in foundation in dry soil i/c lift 1.50M and lead upto 30M i/c all cost of material, labour T&P etc. complete.	500.00	M ³		
2	S/Laying P.C.C. 1:4:8 in foundation of drain and base coat of Road i/c all cost of material, labour T&P etc. complete.	290.00	M ³		
3	I st class Brick work in 1:4 C.M. of Boundry wall i/c all cost of material, labour T&P etc. complete.	225.00	M ³		
4	12 mm Thick Cement Plaster in 1:4 Cement mortar on brick work i/c all cost of material, labour T&P etc. complete.	750.00	M ²		
5	Laying Coping on wall of drain 40mm thick 1:2 course sand.	340.00	M ²		
6	S/Laying of top layer of road in C/m 1 : 2 : 4 i/c all cost of material, labour T&P etc. complete.	190.00	M ²		
7	Supplying and Laying Inter Locking Tiles of thickness 80mm i/c leveling and dressing of surface to required level and slope, filling joints with local sand, all cost of material, Labour, T & P etc. complete.	750.0	M ²		

Sign of Contractor

Address

.....

.....