

## Irrigation Division Moradabad

Name of Work :- जनपद बिजनौर में रामगंगा नदी के दायें किनारे पर शेरपुर रैनी बन्ध के किमी० 0.640 किमी० 1.000 तक पुर्नस्थापना एवं विस्तार का कार्य।

### Schedule-A

Sl. No.	Item of Work	Unit	Quantity	Tendered Rate	
				In Figure	In Word
1	2	3	4	5	6
1	Earth work in embankment (bund) in ordinary soil i/c carriage of earth beyond 1.00 Km. Distance, cost of earth, all labour, T&P and taxes etc. complete with proper manual compaction	cum	23960		

J.E.

A.E.

**Sign of Contractor**

**Address**

.....  
.....  
.....

## AFZALGARH IRRIGATION DIVISION, DHAMPUR

**NAME OF WORK :** Construction Of Boulder Stud No. 4 Near Village Fatehpur Sabhachand & Saifpur  
Khadar On Left Bank Of Ganga River In Distt. Bijnor For The Year 2016-17

### SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1.	Earth work in cutting for making surface of launching apron along bund & stud etc. including all lead & lift ramming complete for one stud.	1400.00	M <sup>3</sup>		
2.	Supply of HDPE/PP Bags (new cement size bag) having size 48 cm x 75 cm i/c cost of material, carriage, loading, unloading, sticking, T&P and taxes etc. required for completion of work.	102000	Nos.		
3.	Supply of T.F. 02 poly proplane multiflament woven GEN textile fabric stitched bag of size 0.69x1.09 M ( G.E.O. Bags) i/c cost of material, carriage, loading, unloading, stricking, T&P and taxes etc. required for completion of work.	5350	Nos		
4.	Filling HDPE/PP bags (new cement size bag) with local earth, sewing with machine & placing in position beyond 1.00 km distance i/c all cost of labour, T&P, royalty and taxes etc. required for completion of work but excluding cost of new bags & nylone rope crate.	102000	Nos.		
5.	Supplying tying of Nylone crates size 0.9x0.9x0.9 M i/c all cost of work.	4600	Nos.		
6.	Filling G.E.O Bags with local earth, Sewing with machine & placing in position beyond 1.00 km distance over cement size bags filled in nylone rope crates i/c labour, T&P, royalty and taxes etc. complete. Required for completion of work but excluding cost of G.E.O bags.	5350	Nos.		
7.	Supplying & Laying, packing boulder 20 to 40 Kg. wt in G.I. wire crate i/c cost of all material, loading, unloading, royalty, staking with all taxes but excluding cost of G.I. wire crate	530.00	M <sup>3</sup>		
8.	Supplying 4 mm G.I. wire crate of size (3.0x1.5x1.0) m, Kuintted with mesh of 15x15 cm, double knot i/c cost of material, labour, and T&P etc	130	Nos.		

**Sign of Contractor**

Address .....  
.....  
.....

## AFZALGARH IRRIGATION DIVISION, DHAMPUR

NAME OF WORK: रामगंगा फीका दोआब नहर के कि०मी० 7.800 पर स्थित पूर्णत क्षतिग्रस्त पुल के स्थान पर नये पुल के निर्माण का कार्य।

### SCHEDULE –‘A’

Sl. No.	Description of work	Approximate quantity	Unit	Tendered Rate in Rs.	
				In figure	In words
1-	Dismantling of Brick Masonry in Cement mortar including stacking of bricks within 60 M distance.	55.00	CUM		
2-	Earth work in excavation in Foundation of V.R.B. in all type of Soil including disposal of excavated earth 60 M distance etc. complete.	635.00	CUM		
3-	Providing & Fixing Centering & Shuttering For R.C.C. Work in V.R.B. including Cost of Labour , T&P etc. complete .	645.00	SQM		
4-	Cement .Concrete. 1:3:6 with crushed stone grit 4mm to 20mm size including cost of all material, Labour, T&P etc. complete of work..	85.00	CUM		
5-	Cement .Concrete. 1:2:4 with crushed stone grit 4mm to 20mm size i/c cost of all material, Labour, T&P etc. complete of work..	290.00	CUM		
6-	Reinforced cement concrete 1:1.5:3 with crushed stone grit 4mm to 20mm size i/c cost of all material, Labour, T&P etc. complete of work..	380.00	CUM		
7-	Reinforced cement concrete 1:1:2 with crushed stone grit 4mm to 20mm size i/c cost of all material, Labour, T&P etc. complete of work..	45.00	CUM		
8-	Supply & Placing Steel Reinforcement For R.C.C. works Including Cost of Material, Cutting, Bending, Binding, Welding etc. Complete of work.	10.00	M.T.		
9-	Making Expansion Joint Including Cost of all Material, Labour , T&P etc. Complete.	25.00	R.M		
10-	Supply and Laying Tarfelt as Tar Paper Bearing etc. complete.	14.00	SQM		
11-	Supplying & Fixing 75 mm Ø G.I. Pipe 0.60 M Long in Drain Spout i/c all Cost of Material ,Labour ,T&P etc. Complete.	5.00	NOS		
12-	Supplying and Laying R.B.M in filter including all Cost of Material ,Labour ,T&P etc. Complete.	15.00	CUM		
13-	Supplying and laying Boulder Pitching with 20 kg. to 40 Kg Wt. Including all Cost of Material ,Labour ,T&P Royalty, taxes etc. complete.	80.00	CUM		
14-	Ist Class Brick work in 1:4 cement mortar i/c all Cost of Material ,Labour ,T&P etc. Complete.	175.00	CUM		
15-	12 mm Thick Cement Plaster with 1:4 Cement Mortar on Brick Work i/c all Cost of Material ,Labour ,T&P etc. Complete.	1600.00	SQM		
16	S/Fixing Sign Board Size (1.50 M X 1.00 M) i/c Cost of all Material , Labour T&P etc Complete.	01	NO		

**Sign of Contractor**

Address .....

.....  
.....