

## IRRIGATION DIVISION, FIROZABAD

Estimate for Constructing Drainage Syphon on Kushwa Drain Crossing at Km. 6.300 Nuh Dy.

### BID OF QUANTITY

S.N.	Name of Item	Qty.	Unit	Rate	
				In Figure	In Word
1	Earth work in foundation including Lift upto 1.5 m. and lead upto 30 m. including back filling watering and ramming	500.00	M <sup>3</sup>		
2	Lean Concrete in 1:4:8 in base of foundation including all labour material T&P complete.	21.00	M <sup>3</sup>		
3	C.C. 1:2:4 in foundation including all material labour T&P complete	61.00	M <sup>3</sup>		
4	R.C.C. 1:1.5:3 in wall ,R.C.C. slab etc. including labour material T&P complete	98.00	M <sup>3</sup>		
5	Centering and Shuttering of R.C.C. work , bridge and syphon etc. complete	262.00	M <sup>2</sup>		
6	1st class Brick work in 1:4 cm. including all material labour T&P complete	10.00	M <sup>3</sup>		
7	Steel reinforcement including labour charges for cutting , bending, binding and placing in Position including cost binding wire.	13.00	MT		
8	Earth work in silt clearance of Drain including all lead & lift.	2664.00	M <sup>3</sup>		
9	Earth work in strengthening bank on Dy including all lead and lift.	747.00	M <sup>3</sup>		
10	Brick Flooring 11cm thick over 12mm thick mortar	24.00	M <sup>2</sup>		
11	Dewatering of Dy for Construction Syphon.	1.00	job		
12	Plaster 1:3 cm including all labour material T&P complete	26.00	M <sup>2</sup>		

Junior Engineer  
Irrigation Division  
Firozabad

Asstt. Engineer  
Irrigation Division  
Firozabad

Executive Engineer  
Irrigation Division  
Firozabad

Contractor