

**DEPARTMENT OF IRRIGATION & WATER RESOURCES, U.P.
DRAINAGE DIVISION, SHAMLI (MUZAFFARNAGAR)**

SCHEDULE-A

NAME OF WORK: CONSTRUCTION OF BOULDER PITCHING FROM K.M. 2.475 TO K.M. 2.835 OF UDPUR SALAHAPUR MARGINAL BUND ON LEFT BANK OF RIVER YAMUNA IN DISTRICT SHAMLI.

SITUATION OF WORK: UDPUR SALAHAPUR MARGINAL BUND.

TENDER NOTICE No.: 03/S.E./2016-17

LOT No.: 03

EARNEST MONEY:

Sl. No.	NAME OF ITEM	UNIT	QTY	TENDERED RATE	
				IN FIGURE	IN WORDS
1	E.W. in excavation in foundation in all type of soil including all cost of labour, T&P etc. complete.	Cum.	4000		
2	Providing & laying boulder in structure with stacking etc. including cost of all material, labour, carriage T&P etc. all complete.	Cum.	300		
3	Providing & laying dry boulder pitching with 20-40 kg boulder including cost of all material, labour, carriage T&P etc. all complete.	Cum.	550		
4	Providing & laying G.I. wire crate with 8SWG G.I. wire, size 3.00x1.50x1.00 M filled with boulder including cost of G.I. wire crate and boulder, all labour, carriage, T&P etc. all complete.	Nos.	600		
5	Providing & laying filter below boulder Pitching including cost of all material, labour, carriage T&P etc. all complete.	Cum.	180		

SIGNATURE OF CONTRACTOR

**DEPARTMENT OF IRRIGATION & WATER RESOURCES, U.P.
DRAINAGE DIVISION, SHAMLI (MUZAFFARNAGAR)**

SCHEDULE-A

NAME OF WORK: RESTORATION OF LAUNCHING APRON OF SPUR No. 5 OF VILLAGE NAI NAGLA ON THE LEFT BANK OF RIVER YAMUNA IN DISTRICT SHAMLI.

SITUATION OF WORK: IN FRONT OF VILLAGE NAI NAGLA.

TENDER NOTICE No.: 03/S.E./2016-17

LOT No.: 01

EARNEST MONEY:

Sl. No.	NAME OF ITEM	UNIT	QTY	TENDERED RATE	
				IN FIGURE	IN WORDS
1	Providing & laying boulder in structure with stacking etc. including cost of all material, labour, carriage T&P etc. all complete.	Cum.	4900		
2	Providing & laying dry boulder pitching with 20-40 kg boulder including cost of all material, labour, carriage T&P etc. all complete.	Cum.	550		
3	Providing & laying G.I. wire crate with 8SWG G.I. wire, size 3.00x1.50x1.00 M filled with boulder including cost of G.I. wire crate and boulder, all labour, carriage, T&P etc. all complete.	Nos.	180.00		

SIGNATURE OF CONTRACTOR

**DEPARTMENT OF IRRIGATION & WATER RESOURCES, U.P.
DRAINAGE DIVISION, SHAMLI (MUZAFFARNAGAR)**

SCHEDULE-A

NAME OF WORK: RESTORATION OF LAUNCHING APRON OF SPUR No. 1 OF VILLAGE UDPUR ON THE LEFT BANK OF RIVER YAMUNA IN DISTRICT SHAMLI.

SITUATION OF WORK: IN FRONT OF VILLAGE UDPUR

TENDER NOTICE No.: 03/S.E./2016-17

LOT No.: 02

EARNEST MONEY:

Sl. No.	NAME OF ITEM	UNIT	QTY	TENDERED RATE	
				IN FIGURE	IN WORDS
1	Providing & laying boulder in structure with stacking etc. including cost of all material, labour, carriage T&P etc. all complete.	Cum.	4850		
2	Providing & laying dry boulder pitching with 20-40 kg boulder including cost of all material, labour, carriage T&P etc. all complete.	Cum.	550		
3	Providing & laying G.I. wire crate with 8SWG G.I. wire, size 3.00x1.50x1.00 M filled with boulder including cost of G.I. wire crate and boulder, all labour, carriage, T&P etc. all complete.	Nos.	180.00		

SIGNATURE OF CONTRACTOR

**DEPARTMENT OF IRRIGATION & WATER RESOURCES, U.P.
DRAINAGE DIVISION, SHAMLI (MUZAFFARNAGAR)**

SCHEDULE-A

NAME OF WORK: ANTI EROSION WORKS BETWEEN K.M. 1.500 TO K.M. 2.150 OF UDPUR SALAHAPUR MARGINAL BUND ON LEFT BANK OF RIVER YAMUNA IN DISTRICT SHAMLI.

SITUATION OF WORK: UDPUR SALAHAPUR MARGINAL BUND

TENDER NOTICE No.: 03/S.E./2016-17

LOT No.:

EARNEST MONEY:

Sl. No.	NAME OF ITEM	UNIT	QTY	TENDERED RATE	
				IN FIGURE	IN WORDS
1	E.W. in excavation in foundation in all type of soil including all cost of labour, T&P etc. complete.	Cum.	4000		
2	Laying New E.C. bags filled with local sand in Nylon crate size (1.00x1.00x1.00 m) with sewing & Placing in position including cost of material &labour etc. complete.	Nos.	36500		
3	Supplying of G.E.O. bags (size 1.09m x 0.69m) including cost of material etc. complete.	Nos.	68000		
4	Filling, Sewing, Placing G.E.O. bags with sand with labour T&P etc. complete	Nos.	68000		
5	Providing & Placing Porcupine on G.E.O. bags plugging including cost of material labour T&P etc. complete.	Nos.	240		
6	Providing Bamboo 5.00 cm.to 8.00 cm. dia with all complete.	R.M.	37000		
7	Bracing of Bamboo Screen including all fitting complete for work in Water.	R.M.	37000		
8	Providing of G.I. Wire 8 S.W.G.at site for binding Porcupine i/c all complete.	Kg.	500		
9	Supplying and Filling Jhankar or Jhau in bundles of 30.00 cm. dia and 1.30 M Long Placing in position i/c Carriage up to 5.00 K.M. i/c all complete.	Bundles	25000		
10	Earth Work in Embankment in Ordinary Soil including lift Up to 1.50 m and Lead Up to 30.00 m i/c all complete.	Cum.	4000		

SIGNATURE OF CONTRACTOR